

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
ARTICLE 1. TITLE, SCOPE AND GENERAL CONDITIONS	1-1
1.0 General Provisions	1-1
1.0.1 Title.....	1-1
1.0.2 Purpose	1-1
1.0.3 Applicability	1-1
1.0.4 Authority Representation.....	1-1
1.0.5 Alternate Materials and Methods of Construction	1-1
1.0.6 Modifications	1-1
1.0.7 Tests.....	1-1
1.0.8 Interpretation and Enforcement.....	1-2
1.0.9 Liability	1-2
1.0.10 Prohibited Actions	1-2
1.0.11 Emergency Work.....	1-2
1.0.12 Insurance Requirements	1-2
1.1 Conditions of the Work	1-4
1.1.1 Working Hours.....	1-4
1.1.2 Emergencies	1-4
1.1.3 Daily Cleanup	1-4
1.1.4 Final Cleanup	1-4
1.1.5 Maintenance Bond	1-4
1.1.6 Authority of the JCWSA.....	1-4
1.1.7 Authority and Duties of Inspector	1-4
1.1.8 Contractor’s Responsibility for Work	1-5
1.1.9 Removal of Unacceptable Work.....	1-5
1.1.10 Scheduling of Work	1-5
1.1.11 Samples and Tests.....	1-5
1.1.12 Storage of Materials	1-5
1.1.13 Defective Materials.....	1-5
1.1.14 Local Laws, Ordinances and Codes	1-5
1.1.15 Public Convenience and Safety	1-5
1.1.16 Location of Existing Utilities	1-6
1.1.17 Protection and Restoration of Property and Survey Monuments.....	1-6
1.1.18 Use of Explosives	1-6
1.1.19 Protection of Streams, Lakes and Reservoirs.....	1-6
1.1.20 Dust Control	1-6
1.1.21 Use of Authority Water	1-6
1.1.22 Maintenance of Drainage	1-6
1.1.23 Interruption of Services	1-7
1.1.24 Equipment Operated on Streets.....	1-7
1.1.25 Material Submittals.....	1-7
1.1.26 Operation of Authority Systems	1-7
1.2 Approvals and Inspections	1-7
1.2.1 Procedures for Development of Water and/or Wastewater Extensions.....	1-7
1.2.2 Preliminary Application.....	1-7

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.2.3 Board Approval of Preliminary Application	1-7
1.2.4 System Engineering Application	1-7
1.2.5 Application for Acceptance	1-8
1.2.6 Suspension or Revocation of Permits	1-8
1.2.7 Approved Plans	1-9
1.2.8 GA EPD, GA DOT, and JCU DC Standards	1-9
1.2.9 NPDES for Stormwater Monitoring	1-9
1.2.10 Construction Inspection	1-9
1.2.11 Additional Inspections and Re-inspections	1-9
1.2.12 System Ownership	1-10
1.3 Fees	1-10
1.3.1 Preliminary Application Fee	1-10
1.3.2 System Engineering Application Fee	1-10
1.3.3 Water Connection Fees	1-10
1.3.4 Wastewater Connection Fees	1-10
1.3.5 Investigation Fees	1-11
1.3.6 Water and Wastewater Usage	1-11
1.4 Plans and Specifications	1-11
1.4.1 General	1-11
1.4.2 General Plan Requirements	1-11
1.4.3 Plan Sheet Requirements	1-12
1.4.4 Profile Sheet Requirements	1-12
1.4.5 Specifications and Support Documentation	1-13
1.5 Definitions and Abbreviations	1-13
1.5.1 Definitions	1-13
1.5.2 Abbreviations	1-14
1.5.3 Terms	1-15
1.5.4 Specifications by Reference	1-15
ARTICLE 2. TITLE, WATER SUPPLY FACILITIES	2-1
2.0 General Provisions	2-1
2.0.1 Applicability	2-1
2.0.2 Approval Process	2-1
2.0.3 Water Supply Construction Plans	2-2
2.0.4 Water Connection Fee	2-3
2.0.5 Proof of Payment	2-3
2.0.6 Letter of Credit	2-3
2.0.7 Tapping Existing Water Mains	2-3
2.0.8 Trenching, Backfilling and Compacting	2-3
2.0.9 Cross Connection Control Program	2-3
2.0.10 Mandatory Backflow Prevention Installations	2-6

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
2.1 Design Criteria	2-7
2.1.1 General.....	2-7
2.1.2 Design Flow Requirements	2-7
2.1.3 Operating Pressure Requirements.....	2-7
2.1.4 Water Main Sizes	2-7
2.1.5 Fire Hydrant Locations	2-8
2.1.6 Spacing of Fire Hydrants.....	2-8
2.1.7 Separate Fire Lines	2-8
2.1.8 Fire Line to Non-residential Area	2-9
2.1.9 Hose Lay	2-9
2.1.10 Fire Main Size	2-9
2.1.11 Distribution System Layout	2-9
2.1.12 Location of Water Lines and Fixtures.....	2-9
2.1.13 Valve Spacing	2-10
2.1.14 Combination Air Valves	2-10
2.1.15 Blow-off Assemblies	2-10
2.1.16 Pipe	2-10
2.1.17 Hydraulic Design	2-10
2.1.18 Minimum Depth	2-10
2.1.19 Water Service	2-10
2.1.20 Water Service Lines	2-11
2.1.21 Water Service Size.....	2-11
2.1.22 Meters	2-11
2.1.23 Location of Meters and Remote Readouts.....	2-12
2.1.24 Meter Size	2-12
2.1.25 Curb Stops	2-12
2.1.26 Pressure Regulators.....	2-12
2.1.27 Pressure Booster Systems.....	2-12
2.1.28 Service Line Stub-Ins	2-13
2.1.29 Service Line Taps.....	2-13
2.1.30 Meter Check Valves	2-13
2.1.31 Pumping Facilities	2-13
2.2 Materials	2-14
2.2.1 General.....	2-14
2.2.2 Pipe	2-14
2.2.3 Joints	2-14
2.2.4 MJ Fittings	2-14
2.2.5 Gate Valves.....	2-15
2.2.6 Butterfly Valves	2-15
2.2.7 Pressure Reducing/Sustaining Valves (PRV/PSV).....	2-15
2.2.8 Fire Hydrants	2-16
2.2.9 Valve Boxes	2-17
2.2.10 Combination Air Release Valves.....	2-17
2.2.11 Blow-off Assembly	2-17
2.2.12 Vaults	2-18
2.2.13 Manholes	2-18
2.2.14 Manhole Base Slabs and Base Beams.....	2-18

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
2.2.15 Sump Pits for Vaults and Manholes	2-18
2.2.16 Vent Pipes	2-18
2.2.17 Mechanical Joint Restraints	2-18
2.2.18 Bedding Materials.....	2-18
2.2.19 Concrete	2-18
2.2.20 Steel Casings for Bores.....	2-18
2.2.21 Service Line Equipment and Materials.....	2-18
2.3 Water Main Construction	2-20
2.3.1 General.....	2-20
2.3.2 Pipe Installation	2-20
2.3.3 Alignment and Grade	2-20
2.3.4 Thrust Blocks.....	2-21
2.3.5 Mechanical Joint Restraints	2-21
2.3.6 Setting Valves and Hydrants.....	2-21
2.3.7 Steel Casing and Carrier Pipe Installation	2-22
2.3.8 Plugging of Dead Ends	2-22
2.3.9 Filling and Venting the Line	2-22
2.3.10 Disinfection and Flushing Mains	2-22
2.3.11 Leakage Testing.....	2-22
2.3.12 Tracer Wire.....	2-23
2.3.13 Trenching	2-23
ARTICLE 3. WASTEWATER FACILITIES	3-1
3.0 General Provisions	3-1
3.0.1 Applicability	3-1
3.0.2 Approval Process	3-1
3.0.3 Construction Plans	3-2
3.0.4 Trench, Backfilling and Compacting	3-3
3.0.5 Preservation of Monuments	3-3
3.0.6 Connection to Authority Wastewater System.....	3-3
3.0.7 Connection to Authority Wastewater System from an Outside Entity.....	3-3
3.1 Design Criteria.....	3-3
3.1.1 Design Flow	3-3
3.1.2 Hydraulic Design	3-4
3.1.3 Wastewater Mains Slope Requirements.....	3-4
3.1.4 Cover.....	3-4
3.1.5 Sewer Line Parallel to Creek.....	3-5
3.1.6 Wastewater Main Extension.....	3-5
3.1.7 Manholes.....	3-5
3.1.8 Wastewater Service Connections	3-5
3.1.9 Location Details.....	3-6
3.1.10 Relation to Water Mains.....	3-6
3.1.11 Grease Interceptors	3-6
3.1.12 Sand and Oil Traps	3-6
3.1.13 Grinder Pumps	3-7

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
3.2	Materials 3-7
3.2.1	Wastewater Pipe 3-7
3.2.2	Plugs..... 3-8
3.2.3	Manholes and Riser Rings 3-8
3.2.4	Manhole Base Slabs and Base Beams..... 3-9
3.2.5	Concrete 3-9
3.2.6	Manhole Rings and Covers..... 3-9
3.2.7	Bedding Materials..... 3-9
3.2.8	Steel Casings for Bores..... 3-9
3.3	Wastewater Main Installation..... 3-9
3.3.1	General..... 3-9
3.3.2	Alignment and Grade 3-9
3.3.3	Handling Pipe and Fittings 3-10
3.3.4	Wastewater Line Installation 3-10
3.3.5	Connections to Existing Manholes 3-10
3.3.6	Construction of Manholes and Clean-Outs 3-10
3.3.7	Steel Casing and Carrier Pipe Installation 3-11
3.3.8	Wyes and Risers for Service Connections..... 3-11
3.3.9	Testing and Inspection 3-11
3.4	Wastewater Service Lines 3-13
3.4.1	Wastewater Service Line General Requirements 3-13
3.5	Wastewater Lift Stations..... 3-14
3.5.1	General..... 3-14
3.5.2	Design Approach..... 3-14
3.5.3	Lift Station Submittal Checklists..... 3-15
3.5.4	Lift Station Type and Design Capacity 3-15
3.5.5	Lift Station Design Criteria 3-15
3.6	Force Mains 3-22
ARTICLE 4. SITE WORK AND EARTHWORK..... 4-1	
4.0	General Provisions 4-1
4.1	General..... 4-1
4.1.1	Disposal..... 4-1
4.1.2	Compaction Testing 4-1
4.2	Materials 4-1
4.2.1	Pipe Bedding Materials Disposal 4-1
4.2.2	Structure Backfill Material 4-1
4.2.3	Asphalt Paving 4-1
4.3	Demolition and Removal of Structures and Obstructions 4-2
4.3.1	General..... 4-2

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
4.3.2 Removal of Pipe	4-2
4.3.3 Removal of Pavements, Sidewalks, and Curbs	4-3
4.4 Site Preparation	4-3
4.4.1 General	4-3
4.4.2 Clearing	4-3
4.4.3 Topsoil	4-3
4.5 Earthwork	4-3
4.5.1 General	4-3
4.5.2 Definitions	4-4
4.5.3 Grading Tolerances	4-4
4.5.4 Excavation	4-5
4.5.5 Fills and Embankments	4-6
4.5.6 Structural Backfill	4-6
4.5.7 Borrow	4-7
4.6 Trenching, Backfilling and Compacting	4-7
4.6.1 General	4-7
4.6.2 Connections to Existing Facilities	4-7
4.6.3 Trench Excavation for Pipelines and Service Lines	4-7
4.6.4 Removal of Water	4-8
4.6.5 Preparation of foundation for Pipe Laying	4-8
4.6.6 Bedding for pipelines and service lines	4-8
4.6.7 Backfill for pipelines and service lines	4-8
4.6.8 Compaction	4-9
4.6.9 Compaction Testing	4-9
4.6.10 Maintenance of Backfill	4-9
4.7 Pavement Replacement	4-9
4.8 Site Restoration	4-9
4.8.1 Restoration	4-9
ARTICLE 5. CONCRETE WORK	5-1
5.0 Applicability	5-1
5.1 General	5-1
5.1.1 Standards	5-1
5.1.2 Submittals	5-1
5.2 Design Criteria	5-1
5.2.1 Mix Design	5-1
5.2.2 Reinforcement Clearances	5-2
5.3 Materials	5-2
5.3.1 General	5-2

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
5.3.2 Cement.....	5-2
5.3.3 Portland Cement Concrete Pavement-Materials	5-2
5.3.4 Fly Ash	5-3
5.3.5 Water.....	5-3
5.3.6 Admixtures	5-3
5.3.7 Fine Aggregate.....	5-3
5.3.8 Coarse Aggregate	5-4
5.3.9 Mixing	5-4
5.3.10 Reinforcing Steel	5-4
5.3.11 Joint Filler Material	5-4
 5.4 Concrete Construction.....	 5-4
5.4.1 Formwork	5-4
5.4.2 Reinforcing Steel.....	5-5
5.4.3 Placing Concrete	5-5
5.4.4 Joints	5-5
5.4.5 Finishing	5-5
5.4.6 Curing.....	5-5
5.4.7 Cold Weather Concreting.....	5-6
5.4.8 Hot Weather Concreting.....	5-6
5.4.9 Backfilling	5-6
5.4.10 Testing.....	5-6

APPENDICES

APPENDIX A: PROCEDURES AND FORMS

Developer Application Flowchart.....	A-1
Preliminary Application	A-2
Water and/or Wastewater Extension Application	A-3
Application Process and Tap Reservation and Payment Policy	A-4
Industrial Questionnaire.....	A-5
Wastewater Treatment Services Contract.....	A-6
Modular Plant Wastewater Services Contract.....	A-7

APPENDIX B: PLAN REVIEW CHECKLISTS

Preliminary Water Review Checklist	B-1
Preliminary Sewer Review Checklist.....	B-2
Water System Extension Application Review Checklist	B-3
Gravity Sewer Extension Application Review Checklist	B-4
Sewer Pump Station Extension Application Review Checklist.....	B-5

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
APPENDIX C: WATER DETAILS	
Utility Placement	C-1
Waterline Location in Cul De Sac	C-2
Water & Sewer Clearance	C-3
Typical Meter Placement	C-4
¾' Residential Meter	C-5
1" Meter Detail	C-6
Buried Gate Valve	C-7
Buried Butterfly Valve	C-8
Typical Fire Hydrant Assembly	C-9
Dead End Fire Hydrant Assembly	C-10
Stub & Plug For Future Connection	C-11
Pipe Bedding Details	C-12
Thrust Blocks	C-13
Thrust Collar	C-14
Bored Highway Crossing	C-15
Air Release Valve Manhole	C-16
Double Check Valve Vault	C-17
RPZ Backflow Preventer	C-18
Fill Valve Assembly	C-19
Pavement Patch & Valve Marker	C-20
APPENDIX D: SANITARY SEWER DETAILS	
Manhole Details	D-1
Doghouse Manhole	D-2
Manhole Cover	D-3
Sewer Service Stub	D-4
Sewer Lateral Connection	D-5
Sewage Air Release Valve Manhole	D-6
Submersible Sewage Pump Station	D-7
Grease Interceptor	D-8
Sand and Oil Interceptor	D-9
Pipe Bedding Details	D-10
APPENDIX E: SITEWORK AND EARTHWORK DETAILS	
Submersible Pump Station Site Layout	E-1
Site Fencing	E-2
APPENDIX F: POLICIES AND ORDINANCES	
Grease Trap Ordinance	F-1
Residential Sewer Easement, Easement Sewer Line, & Sewer Capacity Upgrade Policy	F-2
Modular Plant Policy	F-3